## **BILL OF QUANTITY**

## Name of Work: Supply, Installation Testing and commissioning of Split AC at the chamber of Dean student affairs office at in IITG Campus

SI No	Description	Unit	Qty	Rate (₹)	Rate in figure	Amount (₹)
	Part A : Supply of AC			, <i>i</i>		
1.0	2 TR 5 star rated Split Inverter type room Air Conditioner (For Cooling) having Rotary -R410a/R32 Compressor, Power supply 230V AC, 50HZ, Power Input:1600W or less, Running current :7.3 amp or less, Speed setting (Cooling/Fan): 4/3, also having features of LDC Remote Operating Control, Electronic Thermostat, Oscillating Lovers, auto air swing, Auto Start, ON/OFF timer, Dehumidification, Sleep mode etc	No	3.0			
	Part B : Installation of AC					
2.0	4 KVA Voltage Stabilizer, I/C wiring IDU & ODU	No	3.0			
3.0	Starter Switch	No	3.0			
5.0	Clamp for Outdoor Unit Fitting	No	3.0			
6.0	Copper beyond 4 meter length	meter	4.00			
7.0	Drain pipe 25mm dia CPVC	meter	10.00			
8.0	Installation Charges for Items 1 to 7 as above	No	3.00			
	Total Amount =					
	Discount@%, if any =					
	Net Quoted Amount : Say					
(Rupeesonly						only)