

BOQ
for

Name of Work: Electrical Power Wiring for pump and 18Nos. Insect Killer installed at various locations of Dhansiri Hostel in IITG Campus.						
NIT No: IITG/IPM/NIT/R/2024-25/28, Dated: 09.07.2024						
Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in Words	Amount (Rs.)
1.0	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
	a). 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	Mtr	415			
	b). 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtr	25			
	c). 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Mtr	35			
2.0	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
	a). 5/6 A switch	Each	18			
	b).3 pin 5/6 A socket outlet	Each	18			
	c). 15/16 A switch	Each	1			
	d). 6 pin 15/16 A socket outlet	Each	1			

3.0	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed Conduit as required.					
	a). 25 mm	Mtr	415			
4.0	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.					
	a). 1 or 2 Module (75mmX75mm)	Each	36			
	b). 4 Module (125mmX75mm)	Each	1			
TOTAL AMOUNT						
Discount@.....%, if any						
GRAND TOTAL AMOUNT						
(Rupees.....)						

N.B: Quoted rate should be inclusive of all Taxes.

Date:

Place:

Seal & Signature of Bidder