

BOQ

Repair/Repalcement of Telephone DB boxes & Krone in various locations of IIT Guwahati campus

Sl. No.	Description of Item	Unit	Qty.	Rate (Rs.)	Rate (Rs.) in word	Amount (Rs.)
1	Supply and Installation of Krone Module Copper 10 Pair (Pack of 3)	nos	85.00			
2	Supply of armoured Jelly filled underground telephone cable Make : Finolex,RR kabel,delton or equivalent					
	i) 50 pair 0.5mm Jelly Filled Telephone Cable Armoured	mtr	100			
3	Supply and Installation of 100 pair DB box Material : Mild steel or equivalent	nos	26			
4	Supply and Install of 1200 pair box along with 120 copper Crones (Floor mounted Indoor, 2mm C.R.C.A sheet, Powder coating after chemical Treatment, Bottom &Top, Approved of CPRI certificate IP 65, size : 1500(W) X 1800(H) x350 (D) mm)	nos	1			
					Total Amount	
					Discount @.....%, if any	
					Grand Total	