

BOQ

for

Name of Work: MISC electrical works at New Guest House in IITG Campus.**NIT No: IITG/IPM/NIT/R/2024-25/45, Dated: 24.09.2024**

Sl. No.	Description of Item	Unit	Qty.	Rate (in Rs.)	Rate in Words	Amount (Rs.)
1.0	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.					
	a).Upto 35 sq. mm (clamped with 1mm thick saddle)		Mtr.	270		
2.0	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc., including supplying and fixing ball and socket arrangement, 2 Nos. down rods of 20 mm dia X 1.6 mm thick steel conduit upto 30 cm length, painting and wiring the down rods and connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.		Each	29		
3.0	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed Conduit as required.					
	a). 25 mm		Mtr	275		
4.0	Supply of 3C 2.5 Sq.mm AL flexiable cable. (Make-KEI/Havells/RR Kabel/Finolex/Polycab)		Mtr	270		

5.0	Supply of 36-watt surface/recess mounted LED luminaire (2X2) light fitting. (Make-CG, Cat No-LCTLSNE-36-FO-CDL or equivalent)		No	17		
6.0	Supply of 200watt LED flood light made up of pressure die cast aluminium housing with toughened glass, IP66 protection, SPD 10KV and efficacy more than 100 lm/W. (Make-CG/Philips)		No	12		
7.0	Repairing of pole light with fitting of new LED bulb, Brass holder with necessary accessories as required.		No	12		
TOTAL AMOUNT						
Discount@.....%, if any						
GRAND TOTAL AMOUNT						

(Rupees.....)

N.B: Quoted rate should be inclusive of all Taxes.

Date:

Place:

Seal & Signature of Bidder