

Bill of Quantity						
Name of work : Repairing and Repainting of Table Tennis Room at OLD Sac Building in IITG Campus..						
Item no.	Description of items	Unit	Quantity	Rate(Rs)		Amount (Rs.)
				In Figure	In Words	
1	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.20 mm cement plaster	Sqm	364.80			
2	Distempering with 1st quality acrylic distember (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade :Old work (one or more coats)	Sqm	656.83			
3	Wall painting with premium acrylic emulsion paint (Plastic Paint) of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.Two coats	Sqm	364.98			

4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shadeTwo or more coats on new work.	Sqm	104.28			
5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	Sqm	469.26			
6	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete	Sqm	180.07			

7	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer- in-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.	Sqm	182.40			
	Total Rs.=					
	Rebate if any% Rs.=					
	Grand Total after rebate Rs.=					
	Say Rs.=					

(Rs.....)

Signature of Tenderer