

BOQ

for

Name of Work: Electrification work for newly install 5Nos. AC, 15Nos. water cooler and 12No. washing machine at Subansiri Hostel in IITG Campus.**NIT NO: IITG/IPM/NIT/C/2025-26/03, Dated: 11.04.2025**

Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in Words	Amount (Rs.)
1.0	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
	a). 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Mtr	960			
2.0	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.					
	a). 4 Module (125mmX75mm)	Each	32			
	a). 6 Module (200mmX75mm)	Each	15			
3.0	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
	a). 15/16 A switch	Each	47			
	b). 6 pin 15/16 A socket outlet	Each	47			

4.0	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed Conduit as required.					
	a). 25 mm	Mtr	960			
5.0	Supply and installation of 22Amp DOL Starter with all accessories as required. (Make-Havells/Legrand/L&T)	Each	5			
TOTAL AMOUNT						
Discount@.....%, if any						
GRAND TOTAL AMOUNT						
(Rupees.....)						

N.B: Quoted rate should be inclusive of all Taxes.

Place:

Seal & Signature of Bidder