

Bill of Quantity
for

Replacement of defective Street light SMC box in the Sector -4 area of IITG campus

Sl. No	Description of Item	Unit	Qty.	Rate in Figure	Rate in Word	Amount (Rs.)
1	Suplly and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/recess/pVC conduit as required make Havells/Finolex/RR Kabel or equivalent					
	i) 2 x 1.5 sqmm + 1x 1.5sqmm earth wire	mtr	750.00			
2	Supply and installation of SMC box sizes 295x195x100 mm (syntax/devipolymer/hensel with terminal loop out terminal strips MCBs make Sintex	nos.	72			
3	Supply and fixing 5amps to 32 amp rating 240/415V C curve miniature ckt breaker suitable for inductive load of following poles in the existing MCB DB complete connection testing and commissioing etc as required					
	l) Single pole	pcs	110.00			
4	Supply and making end termination with brass compression gland and alluminium lug for following sizes of PVC insulated and PVC sheated/XLPE aluminum conductor cable of 1.1KV grade as required					
	b) 6 sq.mm 3 core cable	Set	110			
TOTAL AMOUNT						
Discount @.....%, if any						
GRAND TOTAL						

Seal

Signature of the Tenderer

Date :