

BOQ

for

Name of Work: Repairing and repainting of 29 no's student room at C & D block of Subansiri Hostel in IITG Campus**NIT No: IITG/IPM/NIT/R/2024-25/66, Dated: 22.11.2024**

Sl. No.	Description of Item	Unit	Qty.	Rate (in Rs.)	Rate in Words	Amount (Rs.)
1.0	Removing white or colour wash by crapping and sand papering and repairing the surface smooth including necessary repairs to scratches etc. complete	Sqm	1673.01			
2.0	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour Two coats	Sqm	1673.01			
3.0	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work	Sqm	823.89			
4.0	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	58.00			
5.0	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litr	Sqm	58.00			
6.0	Finishing walls with Acrylic Smooth exterior paint of required shade :Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	Sqm	383.96			
TOTAL AMOUNT						
Discount@.....%, if any						
GRAND TOTAL AMOUNT						

(Rupees.....)

N.B: Quoted rate should be inclusive of all Taxes.**Date:****Place:****Seal & Signature of Bidder**