

BILL OF QUANTITY

Name of Work: Supply installation testing commissioning of Split AC current Bio tech park location to be used by school of agricultural and rural technology (SART) at in IITG Campus

SI No	Description	Unit	Qty	Rate (₹)	Rate in figure	Amount (₹)
Part A : Supply of AC						
1.0	2 TR 5 star rated Split Inverter type room Air Conditioner (For Cooling) having Rotary -R410a/R32 Compressor, Power supply 230V AC, 50HZ, Power Input:1600W or less, Running current :7.3 amp or less, Speed setting (Cooling/Fan): 4/3, also having features of LDC Remote Operating Control, Electronic Thermostat, Oscillating Lovers, auto air swing, Auto Start, ON/OFF timer, Dehumidification, Sleep mode etc	No	7.0			
Part B : Installation of AC						
2.0	4 KVA Voltage Stabilizer, I/C wiring IDU & ODU	No	7.0			
3.0	Starter Switch	No	7.0			
4.0	Clamp for Outdoor Unit Fitting	No	7.0			
5.0	Copper beyond 4 meter length	meter	14.00			
6.0	Drain pipe 25mm dia CPVC	meter	14.00			
7.0	Installation Charges for Items 1 to 7 as above	No	7.00			
					Total Amount =	
					Discount@.....%, if any =	
					Net Quoted Amount =	
					Say =	
(Rupees..... only)						

N.B: Quoted rates shall be inclusive of all taxes & GST.