

BOQ
for

Name of Work: Supply and Installation of Exhaust Fans in 108 Washrooms of Old MSH at IITG Campus.

Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (Rs.)	(in	Rate in Words	Amount (Rs.)
1	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.						
a	1 Module (75mmX75mm)	Each	108				
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.						
a	5/6 A switch	Each	108				
3	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick.						
a	Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia. wire and 1.4 mm wide aperture with matching wood beading	sqm	32				
4	Cutting holes of required size in brick masonry wall for fixing of exhaust fan including providing and fixing 300 mm dia PVC pipe conforming BIS-12818 and making good the same etc. complete as per direction of Engineer-in charge.	No	108				
5	Installation, Testing and Commissioning of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.						
a	Upto 450 mm sweep	No	108				
6	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.						
a	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	mtr	388				
7	Supply of five star rated Exhaust fan,300mm light duty make-Havells/Crompton Greaves.	No	108				
TOTAL AMOUNT							
Discount@.....%, if any							
GRAND TOTAL AMOUNT							
(Rupees.....)							

N.B: Quoted rate should be inclusive of all Taxes.

Place:

Seal & Signature of Bidder