

Bill of Quantity
for

Laying of OFC cable inbetween Electrical Substation - 6 to Director Bungalow through HDD method in IITG Campus

Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in Word	Amount (Rs.)
	External work (HDD Method)					
1	Laying of 63mm HDPE pipe by HDD Method less than 1000 Mtr	Mtr.	430			
2	Cable pulling though HDD pipe OFC Cable 35 mm outer dia.	Mtr.	430			
3	Ring chamber 9 900X850) supply and installation with lid and sand filling	Mtr.	5			
4	Supply of 63 mm HDPE pipe as per DOT specification.	Mtr.	430			
5	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	Each	10			
TOTAL AMOUNT						
Discount @%, if any						
GRAND TOTAL						

Seal
Date :

Signature of the Tenderer