

Name of Work: Replacement of 4 inch GI pipeline main from road junction near F-01 to road junction behind F-25 at IITG
Contract No: NIT no. IITG/IPM/NIT/C/2024-25/31, Dated: 06.11.2024

Bill of Quantity

Name of the Bidder:						
Sl. No.	Item Description	Qty	Units	Rate in Figure (in Rs.)	Total Amount	Amount In Words
1.0	2	4	5	13	54	55
1.0	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : Above 40 mm nominal bore	210.00	m			
2.0	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work (above ground) 100 mm dia nominal bore	210.00	m			
3.0	Painting (two or more coats) on rain water, soil waste and vent pipes and fittings with aluminium paint of approved brand and manufacture over a priming coat of ready mixed zinc chromate yellow primer on new work : 100 mm diameter pipes	210.00	m			

4.0	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	4.25	cum			
Total Amount						
Discount @.....%, if any						
GRAND TOTAL						