

BOQ**Replacing of defective 120sq.mm, 3.5 core Armoured aluminum UG cable from ESS#07 to D1-D18 feeder pillar along with some miscellaneous work in sector-1**

Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in word (In Rs)	Amount (Rs.)
1	Laying one 1100V power cables of following sizes direct in ground including excavation, sand cushioning, Protective brick covering and refilling etc. as required					
	Above 95sqmm and upto 185 sq.mm	mtr	225			
	upto 35 sq.mm	mtr	120			
2	Laying and fixing of one number PVC insulated/XLPE power cable of 1.1 KV grade of following size on wall surface as required (above 35 sq.mm and upto 95 sq.mm) clamped with 25*3 mm MS flat clamp (HDPE size is 63mm dia)	mtr	12			
3	Supply and embedding following GI pipe (medium class) in ground including trenching(75cm deep) and refilling etc as required					
	a) 65 mm dia	mtr	10.00			
4	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend,couplers etc. conforming to IS 14930, part II complete with fitting and cutting,joining etc. in the existing trench complete as required					
	63mm dia	mtr	12.00			
5	Supplying and fixing cable route marker with 10cm x 10cmx 5mm thick G.I plate with inscription there on,bolted/welded to 35mm x35mmx6mm angle iron,60cm long and fixing the same in ground as required	nos	20.00			
6	Supply of following types and sizes of 1.1 KV grade XLPE insulated aluminium conductor armoured underground cable make Havells/RR kabel/KEI/Finolex					
	i) 120 sq.mm cable,3.5 Core UG aluminum armoured cable	mtr	225			
7	Supply of following types and sizes of 1.1 KV grade XLPE insulated aluminium conductor armoured underground cable make Havells/RR kabel/KEI/Finolex					
	i) 6 sq.mm cable,4 Core UG aluminum armoured cable	mtr	120			
	Total Amount = Rs					
	Discount @.....%, if any					
	Grand Total					

Seal

Date :

Signature of the Tenderer