

**Bill of Quantity**

**Name of the Work: Miscellaneous Electrical works at Technology Complex and Street lights near TC Building and Swimming pool of IITG Campus**

Sl. No.	Items	Unit	Qty.	Rate in Figure (Rs.)	Rate in Words (Rs.)	Amount (Rs.)
1	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
	15/16 A Switch	Nos	6			
	6 pin 15/16 A socket outlet	Nos	6			
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required					
	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Meter	150			
	4 X 6 sq. mm + 2 X 6 sq. mm earth wire	Meter	60			
	4 X 16 sq. mm + 2 X 6 sq. mm earth wire	Meter	90			
5	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc.					
	3 Module (100mmX75mm)	Nos	6			
6	200 W Flood Light	Nos	1			
7	Supplying of 6 sqmm 3 core Alluminium Armoured Cable	Meter	120			
8	Supplying of 1.5 Sqmm Copper round sheathed cable	Meter	20			
9	Supply of 3 Meter Pole -Make Nezone - NZOP 3 - Octagonal	Nos	2			
10	Supply of 7 Meter Pole -Make Nezone - NZOP 3 - Octagonal	Nos	1			
11	Supply of Single arm Bracket	Nos	1			
12	Supply of Garden Light	pcs	2			
13	Supply of 90 W Street Light	pcs	15			
<b>Total amount =</b>						
<b>Discount@. % if any =</b>						
<b>Net Quoted amount =</b>						
<b>Say =</b>						

(Rupees.....)

**N.B: Quoted rates shall be inclusive of all taxes & GST**