

BOQ for						
Name of Work: Supply, Installation, Testing and Commissioning of Flood Lights at the Back Side of Lohit Hostel in the IITG Campus.						
Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in Words	Amount (Rs.)
1	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.					
	Upto 35 sq. mm (clamped with 1mm thick saddle)	Mtr	610			
2	Supplying and fixing DP sheet steel enclosure on surface/ recess along with 25/32 A 240 V "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	Each	4			
3	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 2.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	Each	18			
4	Supply of 90 W wall-mount waterproof LED flood lights as per approved brands. (Approved Make- Syska/Philips/Havells/CG/Bajaj/Kolors)	Each	18			
5	Supply of 2.5 sq. mm 3-core multistrand Copper Conductor, PVC sheathed, 1.1KV grade, power cable	Each	610			
6	Supply, installation, and testing of L&T Make 16/30A single phase timer for LED lights including box etc, as required.	Each	4			
TOTAL AMOUNT						
Discount@.....%, if any						
GRAND TOTAL AMOUNT						
(Rupees.....)						

N.B: Quoted rate should be inclusive of all Taxes.

Place:

Seal & Signature of Bidder